

Notice to Vendors

Sealed proposals will be received by Cherokee County from experienced, qualified vendors who specialize in the following:

REQUEST FOR PROPOSAL 2024-06 **Transfer Court Update**

Sealed Proposals will be accepted until **February 5th, 2024 at 12:00 P.M.** at the Administration Office in the Cherokee County Office Building, 110 Railroad Ave, 2nd Floor, Gaffney, South Carolina 29340. Location of projects is 125 E Floyd Baker Blvd. Gaffney, SC 29341.

Proposal documents may be obtained from Abi Reid at the County Office Building, by email abi.reid@cherokeecountysc.com. Proposals shall be submitted on the form furnished and shall be submitted in a sealed envelope identifying the company name, the RFP title, the RFP number, and the RFP due date on the face of the envelope.

Ballistic wall, door, transaction window and flooring for Transfer Court at the Cherokee County Courthouse.

Cherokee County is accepting proposals to furnish all labor, materials, equipment, and supervision required to complete the above referenced project based on the following scope of work:

1. Demo and dispose of existing ½ high wall and gate
2. Frame new 8' long x 9' high wall including framed openings for one 3/0 x 7/0 door and one 42' wide x 48' high transaction window
3. Furnish and install UL 752 Level 3 fiberglass panels on wall
4. Install and finish sheetrock on wall
5. Furnish and install one 3/0 x 7/0 stain grade ballistic interior wood core door with UL Level 3 and Hollow Metal frame. Door will have one offset view window 6' x 24' on lock side. View glass to be Level 3 LP 1250. Install keypad lockset.
6. Furnish and install one 42' w x 48' h ballistic interior arch & backer transaction window. Unit to have UL 752 Level 3: 1-1/4' LP 1250 (laminated acrylic polycarbonate) glazing fabricated into clear satin anodized aluminum framing. Unit to have black plastic countertop with Level 3 fiberglass, stainless steel recessed currency tray with Level 3 bullet trap and arch & backer for natural sound
7. Paint new sheetrock and trim. Stain or clear finish wood door
8. Furnish and install 83 yards of carpet
9. Clean up and dispose of all construction debris