## **Notice to Vendors**

**Sealed proposals** will be received by Cherokee County from experienced, qualified vendors who specialize in the following:

## **REQUEST FOR PROPOSAL 2024-11**

## **HVAC units in Booking and D-block at CCDC**

Sealed Proposals will be accepted until **May 20<sup>th</sup> at 12:00 P.M.** at the Administration Office in the Cherokee County Office Building, 110 Railroad Ave, 2<sup>nd</sup> Floor, Gaffney, South Carolina 29340. Location of projects is 315 E Dr. LM Rosemond Ln, Gaffney, SC 29340.

Proposal documents may be obtained from Abi Reid at the County Office Building, by email <a href="mailto:abi.reid@cherokeecountysc.com">abi.reid@cherokeecountysc.com</a>. Proposals shall be submitted on the form furnished and shall be submitted in a sealed envelope identifying the company name, the RFP title, the RFP number, and the RFP due date on the face of the envelope.

## D-block and Booking HVAC at Cherokee County Detention Center

1. Provide a turn-key proposal to provide supplementary cooling for D-Block and Booking

D-Block - Add 3-tons of cooling capacity

Booking - Add 2-tons of cooling capacity

- 2. Scope of Work to include all Labor and Materials to install:
- (1) Mitsubishi or equivalent 3-ton high wall evaporator and matching condenser mini split system

High Wall evaporator location TBD.

The condenser will be mounted to equipment rails located on the roof.

(1) Mitsubishi or equivalent 2-ton high wall evaporator and matching condenser mini split system

**High Wall evaporator location TBD.** 

The condenser will be mounted to equipment rails located on the roof.

MHK2 wireless controllers for each system

The controller is to be covered with a metal thermostat box.

Install an Aspen Mini White or comparable mini split condensate pump for each evaporator.

Condensate tubing is to be routed to the roof.

Installation to include

A high-voltage circuit for each condenser

- (2) equipment rails for each condenser
- (2) pitch pockets for refrigeration/condensation lines

Warranty: 1-year LABOR, 1-year PARTS, 5-year COMPRESSOR

**Final Inspection**