

Addendum 1, RFP 20250-27

Cherokee County Law Enforcement Center Evidence Expansion & Security Project

These items were discussed and agreed upon by me and all contractors that the following items will need to be added to the RFP.

6. Hallway-Seal off opening with framing and sheet rock that led into rooms 308 &309.

- A new LED light, comparable to other ceiling lights, will need to be added in this area.
- New 6-inch molding, with walls to be painted.
- Replace the old ceiling with a new ceiling. The new ceiling will be comparable to the existing ceiling in the Law Enforcement Center.
- I will reach out to the City of Gaffney inspector Don Elder and inquire about potential Egress issues in this area.

7. Room 308-Add a wall that will be framed and sheet rocked to seal off sprinkler room. Cut an opening into the hallway to allow access into sprinkler room. This will be a case opening.

- A new LED light, comparable to other ceiling lights, will need to be added in this area.
- New 6-inch molding, with walls to be painted.

8. Room 308 & 309-Remove two walls and 2 doors & frame in these rooms. The existing drop down ceiling will need to tie into the existing drop ceiling once this wall is removed.

- New 6-inch molding, with walls to be painted.
- Replace the old ceiling with a new ceiling. The new ceiling will be comparable to the existing ceiling in the Law Enforcement Center.

9. Room 309-Remove carpet and glue from the floor. Seal off two windows with .25-inch steel plates.

- New 6-inch molding, with walls to be painted.
- Replace the old ceiling with a new ceiling. The new ceiling will be comparable to the existing ceiling in the Law Enforcement Center.

11. Narcotics Lobby-Add a wall that will create a passageway into narcotics. An existing light will need to be moved and centered in this passageway. The drop-down ceiling will need to be reworked to accommodate new light.

- The new added wall will accommodate two door openings and a frame. These two doors will be comparable to existing doors in the building. The two doors will open into the newly created work area.
- Inside this workspace a new wall will be added to create 2 separate work areas. The new wall will be made to allow the two new areas to be about equal in size. Light fixtures will need to be shifted to accommodate lighting in one of the rooms. Two new lights will need to be added to the other room. The lights will be comparable to the existing lights in the building. At least two new electrical outlets will be added in each of the two new work areas (4 total outlets). Also, light switches will need to be added to each of the newly established rooms. The existing drop down ceiling made to be reworked to accommodate new walls.
- Additionally, HVAC air vents and return air vents may need to be moved, or new vents may need to be added.
 - ❖ Replace the old ceiling with a new ceiling. The new ceiling will be comparable to the existing ceiling in the Law Enforcement Center.
 - ❖ Paint all walls & door frame. Add molding in new rooms.
 - ❖ Take out old lighting and add 5 new LED lights into this area.
 - ❖ Take out sliding glass window. Frame, sheet rock and paint were sliding glass existed.
 - ❖ I will reach out to the City of Gaffney inspector Don Elder and inquire about if new fire sprinklers are required for this area.

To make sure all are aware, the following is not a part of the RFP. I will handle the following:

- Anything concerning the moving/adding/deleting of HVAC issues.
- Anything concerning our key fob system.
- Anything concerning adding/removing CAT5/6 cabling.
- Anything concerning the addition of cameras.
- I will reach to City of Gaffney inspector Don Elder about sprinklers and egress .If sprinklers are needed, I will coordinate with vendor to have these added.