

Addendum 2, RFP 20250-27

- 11. Narcotics Lobby**-Add a wall that will create a passageway into narcotics. An existing light will need to be moved and centered in this passageway. The drop-down ceiling will need to be reworked to accommodate new light.
- The new added wall will accommodate two door openings and a frame. These two doors will be comparable to existing doors in the building. The two doors will open into the newly created work area.
 - Inside this workspace a new wall will be added to create 2 separate work areas. The new wall will be made to allow the two new areas to be about equal in size. Light fixtures will need to be shifted to accommodate lighting in one of the rooms. Two new lights will need to be added to the other room. The lights will be comparable to the existing lights in the building. At least two new electrical outlets will be added in each of the two new work areas (4 total outlets). Also, light switches will need to be added to each of the newly established rooms. The existing drop down ceiling made to be reworked to accommodate new walls.
 - Additionally, HVAC air vents and return air vents may need to be moved, or new vents may need to be added.

❖ In reference to this area, this area will be completed as advertised in the original RFP. There was some confusing about the scope of work to be completed.

1. **Room 308 & 309**-Remove two walls and 2 doors & frame in these rooms. The existing drop down ceiling will need to tie into the existing drop ceiling once this wall is removed.
2. **Room 309**-Remove carpet and glue from the floor. Seal off two windows with .25-inch steel plates.

❖ In reference to this area room 308, 309, 310, specifically the flooring. We still want all the flooring removed in these areas. We want Luxury Vinyl Plank Flooring to be put done in the area where previous flooring is to be removed.